



Uncompromising Standards

QUALITY CONTROL FOR LUXURY
HOSPITALITY VENEER
ARCHITECTURAL MILLWORK

A BEHIND-THE-SCENES LOOK AT OUR RIGOROUS DAILY
INSPECTION PROTOCOL



VENEER LEAF WIDTH CALIBRATION
PRIME GRADE STANDARD: ≥ 100 MM
(APPROX. 4") LEAF WIDTH

THICKNESS CALIBRATION

CUSTOM THICKNESS TOLERANCE CHECK
MICROMETER TOLERANCE LIMIT: ± 0.02
MM (± 0.0008 ") MAX ALLOWANCE



LENGTH VERIFICATION

VENEER LEAF LENGTH VERIFICATION
PRIME GRADE STANDARD: ≥ 2.5 M
(APPROX. 8.2') LEAF LENGTH



MOISTURE MEASUREMENT



EQUILIBRIUM MOISTURE CONTENT (EMC)
CONTROL

TARGET MOISTURE RANGE: 8% – 15% MOISTURE
CONTENT (MC)



5 GRAIN & STRUCTURE CHECK

GRAIN STRAIGHTNESS & ALIGNMENT

GRAIN SPECIFICATION: DEAD-STRAIGHT /
ZERO SWEEP & SLOPE

BATCH LABELING

BATCH LABEL & TRACEABILITY VERIFICATION
VERIFICATION CHECKLIST: DIMENSIONS /
GRADE / BATCH MATCH VERIFICATION



MEET YOUR
QUALITY
ASSURANCE
INSPECTOR

Melody

— Lead Quality Assurance
Inspector at theShaper



Leading Building Materials Supply Chain Partner in Vietnam



+84-703-278-483



andre.c@theshaperworks.com



<https://theshaperworks.com>

